



Condition precedent for installation the HiScan

1. Room
Normal room temperature 22°C
Humidity: 40 - 60%
vibration free floor
weight of the machine: ca. 80 kg
no direct light to the system
no heating near system
2. Table
must be solid to 100 kg
3. Electricity supply
220/230 V V
50 - 60 Hz, 5 A
no disturbance
3 socket with integrated on/out switch
4. Dimensions
look at the picture

The delivery is freely pavement. The client is responsible for the transport to the installation place.

Technical change is possible. Dated: November 2003.